

RENOVATION WORK AT MANOVIKAS KENDRA ROOM NO. 27 B&C

SL. NO.	DESCRIPTION OF ITEM	UNIT	QTY.	RATE	AMOUNT
1	Dismantling of existing steel window at 2nd floor and removal of scrap upto 75 metre.	Sqm	28		
2	20mm thk Plaster with cement sand mortar (1:6)	Sqm	25		
3	Vinyl flooring, wooden colour matt finished or matching with existing colour (as per authorised direction) ,(Give the rate with proper specification)	Sqm	150		
4	Wall putty	Sqm	25		
5	Two coats primer and two coats paint (premium gloss enamel)	Sqm	270		
6	Supplying, fabricating, fixing and finishing with 5mm thk. Clear glass, hifco hinges, Z handle, rebar, L angle 3.4 Z thick natural anodized aluminium Z section window including all the labour and necessary fittings. Frame :- Aluminium extrusion - Hindal make and anodizing by APPEX / ILKA Grade - 43	Sqm	28		
7	Supplying, fitting and fixing of roller window blinds. As per authorised direction. (Give the rate with proper specification)	Sqm	28		
8	Repaire work of 18mm thk. Marble floor at out side of programme hall	Sqm	20		